



हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश - 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 02/2023-24/CUHP/ENGG/NIQ

Dated: 24.05.2023

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for **“Repair maintenance works at Dhauladhar Parisar-2, Dharamshala and artificial turf mat fixing at Dhauladhar Parisar-1, Dharamshala & Shahpur parisar.”** from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be superscribed with the **Name of Work, Quotation Enquiry Ref. No. & Date** and shall reach the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala by registered post or delivered personally latest by **31.05.2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

- 1.) GST certificate.
- 2.) PAN Card.
- 3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
- 4.) Signed copy of terms & conditions (Annexure-I)
- 5.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs. 1,77,896/- (Rupees One Lacs Seventy Seven Thousand Eight Hundred and Ninety Six only).

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in or www.hpcu.ac.in).

Sd/-

Executive Engineer

Central University of Himachal Pradesh
Dharamshala, Distt Kangra. Himachal Pradesh

Copy to:

1. Notice board.
2. University Website.

Sd/-

Executive Engineer

Terms & Conditions

1. The work is to be completed within **10 days**, to be reckoned from the next day from date of award of work.
2. The quantities of work in the schedule (refer **Annexure- 'II'**) are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. L1 bidder has to submit performance security in form of FDR duly pledged in favour of Finance Officer CUHP, Dharamshala @ 5% of awarded amount. This performance security shall be released after a period of six months after completion of work. This performance security has to be submitted within 3 days after awarding of work.
5. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
6. Payment shall be made only after the work is completed as per actual quantity and quantum of work executed satisfactorily; no advance shall be paid.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.
8. Compensation of delay of work will be @ 0.5% per day.
9. The quotation for the work shall have validity for a period of 15 days from the date of opening of quotations.
10. The contractor/firm has to abide by labour rules and regulations.
11. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
12. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
13. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
14. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
15. In case of any queries/doubts the bidder(s) can visit the Office of Executive Engineer, CUHP at Dharamshala.

Sd/-
Executive Engineer
Central University of Himachal Pradesh
Dharamshala, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL): _____

Address:

Contact no:

BILL OF QUANTITIES

Name of Work: Repair maintenance works at Dhauladhar Parisar-2, Dharamshala and artificial turf mat fixing at Dhauladhar Parisar-1, Dharamshala & Shahpur Parisar					
Name of Bidder:					
S. No.	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	32.61		
2	Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	sqm	374.69		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	sqm	412.48		
4	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	sqm	144.13		
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge: With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	24.36		
6	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	sqm	13.80		

7	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like : Cement mortar 1:6 (1 cement : 6 coarse sand) : (Only existing stones to be used for masonry work)	cum	1.620		
8	Removing existing aluminium partitions/doors including glass/panelling and stacking the same upto 50 m lead complete as per site requirement and directions of engineer-in-charge.	sqm	10.86		
9	Fixing of existing aluminium partitions/doors including cutting of existing aluminium sections/glass/panelling complete as per site requirements and directions of engineer-in-charge (Cost of EPDM rubber / neoprene gasket, CP brass screws is included in the item).	sqm	10.86		
10	Providing and fixing 35 mm high density weather resistant artificial turf mat/grass carpet in external area on RCC/cement concrete surface with necessary screws, adhesive, complete as required.	sqm	41.03		
				Total (in Rs.)	
	Total Amount in Words:				

Signature of bidder

Name: _____

Address: _____

Sd/-
Executive Engineer
Central University of Himachal Pradesh
Dharamshala, Distt. Kangra, H.P.